

# Waste Treatment Plant Project

## WTP Nuclear Safety Status

Michael Greutman

*WTP Nuclear Safety Manager*

February 2021



# Protecting the environment and the public

## *Clean up of legacy waste dates back decades*



### Product of plutonium production for WWII Manhattan Project and Cold War



**56 million gallons  
radioactive waste**

- 149 single-shell tanks built 1943-1964
- 28 double-shell tanks built 1968-1986
- About 60 tanks presumed to have leaked up to 1 million gallons

# WTP will have four nuclear facilities



**Pretreatment Facility**

**Analytical Laboratory**

**High-Level Waste Facility**

**Low-Activity Waste Facility**



# Low-Activity Waste Vitrification Facility

*Turn low-activity waste into glass in two 300-ton melters*



- Waste and Glass Mixture Heated to 2100 degrees F
- Poured into 4-ft diameter, 7-ft high containers weighing 7 tons
- Produce over 1000 cannisters a year



- 330 feet x 240 feet x 90 feet tall
- 28,500 cubic yards concrete
- 6,200 tons structural steel
- 103,000 feet piping
- 840,000 feet electrical cable
- 945,000 pounds heating and ventilation ductwork

# Analytical Laboratory

## *Ensure glass meets regulatory requirements*



Expected to analyze approximately 3,000 WTP process samples each year



- 320 feet x 180 feet x 45 feet tall
- 12,000 cubic yards concrete
- 1,800 tons structural steel
- 35,000 feet piping
- 172,000 feet electrical cable
- 314,500 pounds heating and ventilation ductwork

- Will provide sampling of direct feed low-activity waste and glass product
- Less than HC-3 Nuclear Facility to support DFLAW, but HC-3 PDSA (HLW/PT Operations).



# Balance of Facilities

## *Vast infrastructure to support operations*



- Steam plant
- Chiller compressor facility
- Electrical substation & switchgear
- Water treatment facility
- Glass-forming material storage
- Emergency power facility
- Cooling tower
- Underground waste transfer systems
- Effluent Management Facility

Will provide the infrastructure needed to produce low-activity glass

# LAW Hazards

- Rad – Consequences to all receptors (Public, CLW, FW) are “Low”
- NO<sub>x</sub> - (Co-mingled with Rad)
- Process Waste (NaOH-like, Co-mingled with Rad)
- NaOH – (Cold Chemical)
- Ammonia – (Cold Chemical, PSM quantities in BOF)
- Mercury – (Separated from process waste, no rad)
- CO<sub>2</sub> – (Cold Chemical, hazard is been eliminated from process)
- All consequences of chemical hazards are limited to FW and CLW with the exception of mercury storage which has a public consequence of concern.

# STD-1228 and CSMP Implementation



	STD-3009-94 CN3	STD-1228 with CSMP Implmentation
DSA Page Count	1789	621
TSR Page Count	604	36
PrHA Page Count	4891	4672
Safety-Significant SSCs	68 (26 interlocks)	0
SACs	20	2

**No controls were eliminated, but reclassified as “Chemical Safety”**



# LAW Safety Basis Status



- **DSA/TSR Rev. 4 Currently in DOE Review**
  - Updates necessary to support Commissioning
  - Incorporation of Revised Waste Acceptance Criteria Approach
  - Close out of Planned Design and Operational Safety Improvements
  - Incorporation of Revised Criticality Safety Evaluation
  - Incorporation of Key-DiD Approach
  
- **Chemical Safety Management Program**
  - Chemical Safety Management Program Description approved by DOE on 01/23/2020
  - Included all program requirements and list of Chemical Safety designated controls and safety functions
  - Uses existing LAW PrHA as base hazard analysis
  - Additional Hazard Analyses developed for chemical hazards outside the scope of the DSA (i.e., BOF Anhydrous Ammonia)
  - Will be revised for consistency with Rev. 4 of the DSA.

# Key LAW Milestones



- Turnover of All Systems to Plant Management Currently Being Completed
- Start Full Cold Commissioning (Loss of Power Test) **October 2021**
- Melter 1 Heat-Up **December 2021**
- DOE ORR Complete **December 2022**
- Hot Commissioning Start **January 2023**

# HLW Facility Status



- Currently at 60% Design for Most Major Systems, mechanical handling systems at pre-90%
- Pre-Treat Feed Design Configuration - Decision on Direct Feed High-Level Waste forecast in 2021, however a decision on PTF is not expected near term
- PDSA and PrHA being updated as systems progress through 60% Design
- Procurement Resumption Forecast in 2023
- Construction Resumption Forecast in 2024